ALL PROJECTIONS AND SCHEDULES ARE SUBJECT TO CHANGE

Road Reconstruction/Overlay projects - UNSCHEDULED, to be done

	sq yds	miles	date of Qa	Qa
Woodstock Ln: Old York Rd-Windy Willow Way	2,037.00	0.116	2/2/2017	5.00
Corliss Ct: Windy Willow Way-70	940.00	0.053	2/2/2017	5.85
Kacey Ct: Windy Willow Way-Windy Willow Way	2,730.00	0.155	2/2/2017	5.75
Whitehall Drive: Windy Willow Way-295	963.00	0.055	2/2/2017	5.40
Salem Ct: Windy Willow Way-243	1,410.00	0.080	2/2/2017	6.25
Stratford Lane: Windy Willow Way-Windy Willow Way	3,120.00	0.177	2/2/2017	4.60
Windy Willow Way: Corliss Ct-Stratford Lane	4,430.00	0.252	2/2/2017	4.10
Windy Willow Way: Kacey Ct-Salem Ct	2,283.00	0.130	2/2/2017	4.10
Windy Willow Way: Manchester Dr-Whitehall Drive	2,777.00	0.158	2/2/2017	4.10
Windy Willow Way: Old York Rd-Windy Willow Way	2,307.00	0.131	2/2/2017	4.10
Windy Willow Way: Salem Ct-Windy Willow Way	2,297.00	0.131	2/2/2017	4.10
Windy Willow Way: Stratford Lane-Corliss Ct	2,517.00	0.143	2/2/2017	4.10
Windy Willow Way: Stratford Lane-Woodstock Ln	873.00	0.050	2/2/2017	4.10
Windy Willow Way: Whitehall Drive-Stratford Lane	3,703.00	0.210	2/2/2017	4.10
Windy Willow Way: Windy Willow Way-Manchester Dr	877.00	0.050	2/2/2017	4.10
Windy Willow Way: Woodstock Ln-Kacey Ct	720.00	0.041	2/2/2017	4.10
Industrial Parkway (county Line Rd): Chatham Rd-Culnen Dr	6,380.00	0.302	2/22/2017	5.85
Industrial Parkway (county Line Rd): County Line Rd-Chatham Rd	6,780.00	0.321	2/22/2017	5.85
Industrial Parkway (county Line Rd): Culnen Dr-135003	2,132.00	0.101	2/22/2017	5.85
Chatham Rd: Industrial Parkway (County Line Rd)-Azalea Terrace	2,975.00	0.145	2/22/2017	7.75
Evans Way: Old York Rd-96001	8,036.00	0.381	8/19/2016	4.05
Evans Way: Old York Rd-96002	2,900.00	0.137	8/19/2016	4.05
Miller Ave.: Darcy Ct-River Rd	1,620.00	0.138	8/18/2016	3.90
Miller Ave.: Station Rd-Darcy Ct	6,082.00	0.518	8/18/2016	3.75
Imclone Dr: Route 202-Chubb Way	10,582.00	0.515	1/30/2017	5.90
Schaffer St				
Crestwood Ave				
Fremont St				

ALL PROJECTIONS AND SCHEDULES ARE SUBJECT TO CHANGE

2021 Projection - Surface Treatment	miles	sq yds	total	cost/sy
Columbia Dr	0.28	5808	$ 27,588.00	$ 4.75
Chambers brook	0.6	12339	$ 58,610.25	$ 4.75
Old Turnpike Rd: Lamington Rd-200	0.16	1221.00	$ 5,799.75	$ 4.75
Central Place	0.18	1323	$ 6,284.25	$ 4.75
Cedar Grove	1.11	19536	$ 92,796.00	$ 4.75
Whiton Rd*	2.03	35728	$ 169,708.00	$ 4.75
Stony Brook - West Cty to Harlan School*	0.58	10290	$ 48,877.50	$ 4.75
Horizon	0.94	16544	$ 78,584.00	$ 4.75
Kelly	0.48	8448	$ 40,128.00	$ 4.75
Omni	0.17	2992	$ 14,212.00	$ 4.75
Renya	0.2	3520	$ 16,720.00	$ 4.75
	6.73	117749	$ 559,307.75	$ 4.75
Black point -Fire house to bridge	0.9	11611	$ 69,666.00	$ 6.00
Woodfern Rd: Main St-Black Point Road	0.661	7,758.00	$ 46,548.00	$ 6.00
*Reconstructed 2014/15				

ALL PROJECTIONS AND SCHEDULES ARE SUBJECT TO CHANGE

2022 Projection - Surface Treatment				
Huyler	0.61	10736	$ 50,996.00	$ 4.75
Henry	0.31	5456	$ 25,916.00	$ 4.75
Robbins	0.58	8166	$ 38,788.50	$ 4.75
Vanderveer Ave: Easton Turnpike (rt 28)-28	0.709	10,819.00	$ 51,390.25	$ 4.75

2022 Projected Road Reconstruction/Overlay projects

Miller Ave. Improvements
Meister Ave West
Meister Ave Connection
Cedar Grove Mill and Pave

NJDOT Grant 2021 Application Holland Brook Road

ALL PROJECTIONS AND SCHEDULES ARE SUBJECT TO CHANGE

2020 Projection - Surface Treatment	miles	sq yds	total	cost/sy
River Rd - Station Rd to Wooden Bridge	0.14	2142	$ 10,174.50	$ 4.75
Darcy Ct	0.12	2132	$ 10,127.00	$ 4.75
Moutainview Terr	0.11	2003	$ 9,514.25	$ 4.75
Winfield Terr	0.21	3693	$ 17,541.75	$ 4.75
Christian Lane	0.14	2487	$ 11,813.25	$ 4.75
Colonial Court	0.11	1913	$ 9,086.75	$ 4.75
Woodside Lane	0.23	4043	$ 19,204.25	$ 4.75
Hidden Lane	0.19	3340	$ 15,865.00	$ 4.75
Parsonage Hill Dr	0.39	6820	$ 32,395.00	$ 4.75
Yorkshire Lane:	0.08	1473	$ 6,996.75	$ 4.75
Falls	0.15	2704	$ 12,844.00	$ 4.75
Clover	0.05	685	$ 3,253.75	$ 4.75
Devon	0.07	1233	$ 5,856.75	$ 4.75
Charlton	0.09	1150	$ 5,462.50	$ 4.75
West County Dr	0.29	6027	$ 28,628.25	$ 4.75
Macintosh Rd	0.17	2614	$ 12,416.50	$ 4.75
Dana	0.14	2187	$ 10,388.25	$ 4.75
Cascades Terr	0.3	4518	$ 21,460.50	$ 4.75
Carlisle Rd	0.19	2863	$ 13,599.25	$ 4.75
Mohave Tr	0.03	427	$ 2,028.25	$ 4.75
Ramapo Tr	0.19	3002	$ 14,259.50	$ 4.75
Cheyenne Tr	0.11	1595	$ 7,576.25	$ 4.75
Apache Way	0.07	1077	$ 5,115.75	$ 4.75
Pohatan Lane:	0.05	684	$ 3,249.00	$ 4.75
Watchung Trail	0.07	1029	$ 4,887.75	$ 4.75
Munsee Trail:	0.03	456	$ 2,166.00	$ 4.75
Samson Court	0.06	872	$ 4,142.00	$ 4.75
Huron Trail	0.08	1238	$ 5,880.50	$ 4.75
Hopi Trail	0.03	550	$ 2,612.50	$ 4.75
Tuscarora Trail	0.11	1695	$ 8,051.25	$ 4.75
Dakota Trail	0.12	1780	$ 8,455.00	$ 4.75
Mohegan Trail:	0.05	708	$ 3,363.00	$ 4.75
Heritage Ct	0.09	1453	$ 6,901.75	$ 4.75
Nicholas Ct	0.13	2128	$ 10,108.00	$ 4.75
Gates	0.13	1374	$ 6,526.50	$ 4.75
Mitchell	0.13	1221	$ 5,799.75	$ 4.75
Main st (by post office)	0.1	1666	$ 7,913.50	$ 4.75
Olive and Pearl	0.28	5000	$ 23,750.00	$ 4.75
Stony Brook (West cty to Harlan School	0.58	10253	$ 48,701.75	$ 4.75
Barton	0.35	6197	$ 29,435.75	$ 4.75
Laggren	0.2	3540	$ 16,815.00	$ 4.75
Woodfern - Blackpoint to Post Office	0.73	10242	$ 61,452.00	$ 6.00
Woodfern - Lehigh to bridge	0.67	8702	$ 52,212.00	$ 6.00

2020 Projected Road Reconstruction/Overlay projects

Holland Brook Road West estimated completion date: 12/15/20
Stony Brook Road - estimated completion date: 12/15/20
(Hummingbird to Harlan)

NJDOT Grant 2020 Application TBD

*Reconstructed 2012

ALL PROJECTIONS AND SCHEDULES ARE SUBJECT TO CHANGE

2019 Projection - Surface Treatment	miles	sq yds	total	cost/sy
Oak Tavern	0.45	7857	$ 37,320.75	$ 4.75
Bowman Ct	0.06	1027	$ 4,878.25	$ 4.75
Farrington	0.38	6670	$ 31,682.50	$ 4.75
Sturbridge	0.23	3987	$ 18,938.25	$ 4.75
Cheryl Ln.	0.14	2040	$ 9,690.00	$ 4.75
Johns Ln	0.48	7905	$ 37,548.75	$ 4.75
Rays Ct	0.09	1543	$ 7,329.25	$ 4.75
Caruso Ct	0.11	1973	$ 9,371.75	$ 4.75
Bebe ct	0.17	3070	$ 14,582.50	$ 4.75
Bellglade Ct	0.26	4620	$ 21,945.00	$ 4.75
Kip Ln	0.11	1913	$ 9,086.75	$ 4.75
Breezy Point	0.16	2817	$ 13,380.75	$ 4.75
Meadow View	0.19	2733	$ 10,820.50	$ 4.75
Michaels Ct	0.21	3747	$ 4,322.50	$ 4.75
Monica	0.19	2278	$ 14,592.00	$ 4.75
Susquehanna Trail	0.35	5215	$ -	$ 4.75
Chippewa Tr	0.06	924	$ 4,389.00	$ 4.75
Seminole Tr	0.04	560	$ 2,660.00	$ 4.75
Iroquois Trail	0.16	2456	$ 11,666.00	$ 4.75
Blackfoot Tr	0.04	598	$ 2,840.50	$ 4.75
Navajo	0.06	1057	$ 5,020.75	$ 4.75
Spokane	0.05	813	$ 3,861.75	$ 4.75
Algonquin Trail	0.06	850	$ 4,037.50	$ 4.75
Pamlico Path	0.05	710	$ 3,372.50	$ 4.75
Seneca Trail	0.09	1359	$ 6,455.25	$ 4.75
Paiute Trail:	0.04	572	$ 2,717.00	$ 4.75
Leslie Lane	0.03	425	$ 2,018.75	$ 4.75
Pueblo Trail:	0.05	783	$ 3,719.25	$ 4.75
Buffalo Hollow	0.13	1952	$ 9,272.00	$ 4.75
Creek Tr	0.1	1479	$ 7,025.25	$ 4.75
Lenape Tr	0.02	1754	$ 8,331.50	$ 4.75
Yuma Tr	0.13	1902	$ 9,034.50	$ 4.75
Sioux Ln	0.05	725	$ 3,443.75	$ 4.75
Ottawa Tr	0.14	2071	$ 9,837.25	$ 4.75
Cherokee Path	0.05	802	$ 3,809.50	$ 4.75
Winthrop	0.2	3169	$ 15,052.75	$ 4.75
Natures Lane	0.2	3009	$ 14,292.75	$ 4.75
Strawberry Hill	0.32	4879	$ 23,175.25	$ 4.75
Cranbury Rd	0.15	2331	$ 11,072.25	$ 4.75
Mulberry Ct	0.05	780	$ 3,705.00	$ 4.75
Cottage Pl	0.14	2202	$ 10,459.50	$ 4.75
Yellow Jacket	0.03	451	$ 2,142.25	$ 4.75
Oxford Ct	0.03	471	$ 2,237.25	$ 4.75
Lindsay Ct:	0.08	1500	$ 7,125.00	$ 4.75
Sunset	0.21	3720	$ 17,670.00	$ 4.75
Carraige hill	0.35	6036	$ 28,671.00	$ 4.75
Elia Dr	0.07	1333	$ 6,331.75	$ 4.75
Rose way	0.07	1756	$ 8,341.00	$ 4.75
Van Ardsdale	0.55	9666	$ 45,913.50	$ 4.75
Fernande	0.04	727	$ 3,453.25	$ 4.75
Covered Bridge	0.15	3833	$ 18,206.75	$ 4.75
Lehigh	0.62	8725	$ 41,443.75	$ 4.75

2019 Projected Road Reconstruction/Overlay projects

North Branch River Road estimated completion date: 12/15/19
Harlan School Road Section 2 estimated completion date: 12/15/19

NJDOT Grant 2019 Application Cedar Grove Mill Pave + ADA

*Reconstructed 2011

ALL PROJECTIONS AND SCHEDULES ARE SUBJECT TO CHANGE

2018 Surface Treatment	miles	sq yds	total	cost/sy
Arapaho	0.49	10002	$ 47,509.50	$ 4.75
Mohawk	0.33	5790	$ 27,502.50	$ 4.75
			$ -	$ 4.75
Delaware	0.29	4449	$ 21,132.75	$ 4.75
Choctaw Ridge	0.64	11213	$ 53,261.75	$ 4.75
Shoshoni Way	0.16	2694	$ 12,796.50	$ 4.75
Chelsey	0.05	910	$ 4,322.50	$ 4.75
Laurel	0.18	3072	$ 14,592.00	$ 4.75
Carriage Hill	0.35	6036	$ 28,671.00	$ 4.75
Elia Dr	0.07	1333	$ 6,331.75	$ 4.75
Carriage Hill (Arrowhead to Rose way	0.16	2883	$ 13,694.25	$ 4.75
Twin Pines	0.23	3990	$ 18,952.50	$ 4.75
Campana	0.08	1490	$ 7,077.50	$ 4.75
Mathers	0.09	1280	$ 6,080.00	$ 4.75
Settlers Ct	0.1	1807	$ 8,583.25	$ 4.75
Covered Bridge	0.5	9665	$ 45,908.75	$ 4.75
Oak Hill	0.36	6363	$ 30,224.25	$ 4.75
Tamarack	0.26	4504	$ 21,394.00	$ 4.75
Birch	0.05	933	$ 4,431.75	$ 4.75
Harvest	0.15	2766	$ 13,138.50	$ 4.75
Forest Ln	0.15	2643	$ 12,554.25	$ 4.75
Orion	0.14	2483	$ 11,794.25	$ 4.75
Edgewood	0.35	6160	$ 29,260.00	$ 4.75
Ariel	0.05	880	$ 4,180.00	$ 4.75
Beechwood	0.26	4503	$ 21,389.25	$ 4.75
Circle	0.06	851	$ 4,042.25	$ 4.75
Deerhill	0.22	3947	$ 18,748.25	$ 4.75
West County (Stony brook Estates)	0.41	9225	$ 43,818.75	$ 4.75
Starling	0.37	6337	$ 30,100.75	$ 4.75
Lunde	0.15	2590	$ 12,302.50	$ 4.75
	6.7		$ 573,795.25	$ 4.75
Frewert Ln	0.01	1800	$ 23,400.00	$ 13.00
Opie Rd	1.11	14326	$ 85,956.00	$ 6.00
	1.12		$ 109,356.00	
	miles		total	
	7.82		$ 683,151.25	

2018 Road Reconstruction/Overlay projects

Stony Brook Section 1 Road Improvements
Stony Brook Section 6 Road Improvements
Kenbury Road and Drainage Improvements

NJDOT Grant 2018 Application Holland Brook Road West

2017 Surface Treatment	miles	sq yds	total	cost/sy
Acorn Ln	0.21	2219	$ 10,207.40	$ 4.60
Oak Crest	0.2	2335	$ 10,741.00	$ 4.60
Hickory Hill	0.12	1669	$ 7,677.40	$ 4.60
Post	0.21	3700	$ 17,020.00	$ 4.60
Gordon	0.27	4830	$ 22,218.00	$ 4.60
Christie way	0.56	6564	$ 30,194.40	$ 4.60
Benjamin	0.18	3005	$ 13,823.00	$ 4.60
Whiton Rd west 202 to old York	0.31	4673	$ 21,495.80	$ 4.60
Brandon Ct	1.05	18433	$ 84,791.80	$ 4.60
Gregory Ln	0.08	1400	$ 6,440.00	$ 4.60
Elliot	0.08	1470	$ 6,762.00	$ 4.60
Evergreen	0.43	7567	$ 34,808.20	$ 4.60
Windmill	0.47	8287	$ 38,120.20	$ 4.60
Brookview	0.16	2793	$ 12,847.80	$ 4.60
Dow Place	0.08	1632	$ 7,507.20	$ 4.60
Vollers Dr	0.68	12010	$ 55,246.00	$ 4.60
Katherine St	0.13	2207	$ 10,152.20	$ 4.60
Stevens Ave	0.33	5893	$ 27,107.80	$ 4.60
Stony Brook Baird to West County	0.1	5508	$ 25,336.80	$ 4.60
Stony Brook west county to New pavement	0.1	1666	$ 7,663.60	$ 4.60
Mill Lane	0.11	1318	$ 6,062.80	$ 4.60
Pine	0.09	1610	$ 7,406.00	$ 4.60
Walnut	0.25	4397	$ 20,226.20	$ 4.60
River Rd Wooden bridge to stony brook	0.39	6847	$ 31,496.20	$ 4.60
River Rd Logan - Jeffery	0.24	4336	$ 19,945.60	$ 4.60
Cedar Grove River - Preston	0.22	3940	$ 18,124.00	$ 4.60
12 cul-de-sacs		3840	$ 17,664.00	$ 4.60
	7.05			$ 4.60
202 to BOE		1597	$ 7,346.20	$ 4.60
TH rear lot		2000	$ 9,200.00	$ 4.60
North Branch Fire		2511	$ 11,550.60	$ 4.60
Neshanic fire		3255	$ 14,973.00	$ 4.60
	actual	**133,512**	**$ 614,155.20**	$ 4.60
Jeffery Ct Repave	0.13	2700	$ 35,100.00	$ 13.00
	miles		total	
	7.18		$ 649,255.20	

2016 Surface Treatment		miles	sq yds	total	cost/sy
Sunrise	HP chip	0.42	6000	$ 27,600.00	$ 4.60
Highview Ct	HP chip	0.07	1000	$ 4,600.00	$ 4.60
Renda	HP chip	0.11	2000	$ 9,200.00	$ 4.60
Field point	HP chip	0.62	9000	$ 41,400.00	$ 4.60
Village way	HP chip	0.34	6100	$ 28,060.00	$ 4.60
Deerfield	HP chip	0.32	5500	$ 25,300.00	$ 4.60
Briar Way	HP chip	1.01	14500	$ 66,700.00	$ 4.60
Colin Ct	HP chip	0.1	1500	$ 6,900.00	$ 4.60
Richfield Ct	HP chip	0.1	1500	$ 6,900.00	$ 4.60
Crystal Ct	HP chip	0.13	2000	$ 9,200.00	$ 4.60
Old York - Farrington to Bran	HP chip	0.98	24453	$ 112,483.80	$ 4.60
Carrol Jean	HP chip	0.58	10500	$ 48,300.00	$ 4.60
Round Hill Rd	HP chip	0.63	13000	$ 59,800.00	$ 4.60
Libby Ln	HP chip	0.14	2700	$ 12,420.00	$ 4.60
Lukes Pond	HP chip	0.6	11000	$ 50,600.00	$ 4.60
Oriole Ln	HP chip	0.25	3250	$ 14,950.00	$ 4.60
cul-de-sacs 12@314			3768	$ 17,332.80	$ 4.60
		6.4	117771	$ 541,746.60	
Parking lot			1067	$ 4,908.20	$ 4.60
old York to pavers			2667	$ 12,268.20	$ 4.60
					$ 4.60
Upper driveway by 202			950	$ 4,370.00	$ 4.60
			4684	$ 21,546.40	$ 4.60
		miles		total	
		6.4		$ 554,014.80	

2016 Engineering Department Projects
Stony Brook Road Sec 4&5 (Harlan to River)
Meister Ave (West) Reconstruct

Engineering Sanitary Sewer Projects
Baird Road - Design/Build 2015
Preston Sanitary Sewer Investigation 2015
Miller Ave. Sanitary Sewer Investigation 2015/16

2015 Surface Treatment		miles	sq yds	total	cost/sy
Thoroughbred	HP chip	0.5	8800	$ 40,304.00	$ 4.58
Paddock	HP chip	0.09	1700	$ 7,786.00	$ 4.58
Preakness	HP chip	0.37	7000	$ 32,060.00	$ 4.58
Carrol Jean	HP chip	0.58	10500	$ 48,090.00	$ 4.58
Round Hill Rd	HP chip	0.63	13000	$ 59,540.00	$ 4.58
Libby Ln	HP chip	0.14	2700	$ 12,366.00	$ 4.58
Lukes Pond	HP chip	0.6	11000	$ 50,380.00	$ 4.58
Summerfield	HP chip	0.16	3000	$ 13,740.00	$ 4.58
County Line	HP chip	0.51	11000	$ 50,380.00	$ 4.58
Holland Brook West	HP chip	0.73	13000	$ 59,540.00	$ 4.58
Holland Brook	HP chip	0.47	10000	$ 45,800.00	$ 4.58
Hillcrest Drive	HP chip	1.04	22000	$ 100,760.00	$ 4.58
Tecumseh	HP chip	0.23	4500	$ 20,610.00	$ 4.58
Plymouth Ct	HP chip	0.06	1300	$ 5,954.00	$ 4.58
Oriole Ln	HP chip	0.25	3250	$ 14,885.00	$ 4.58
		6.36		$ 562,195.00	
Tanglewood Dr	Mill & Overlay	0.46	8800	$ 114,400.00	$ 13.00
Fairview Dr	clamation & Ove	1	20000	$ 275,000.00	$ 13.75
		miles		total	
		7.82		$ 951,595.00	

Whiton Rd (Tamarack Reconstruction

2015 Engineering Department Projects
Whiton Section 3 & 4 (un/NJDOT Funded
Kenbury Road Drainagunicipally Funded
Design Stony Brook SAntic. NJDOT Funded
Note 2015 apply for NJDOT grant Stony Brook Road Sec 5 (Humming Bird to River)
Survey Stony Brook Sec 4 & 5, and Meister

2014 Surface Treatment		Treatment
Blue Grass Blvd	0.52	HP chip
Fox Chase Run	0.33	HP chip
France Drive	0.27	HP chip
Greenwood Ct	0.13	HP chip
Katydid Drive	0.39	HP chip
Long Meadow Ct	0.12	HP chip
Ronan Way	0.83	HP chip
Shale Hill	0.14	HP chip
Sheephill Circle	0.04	HP chip
Snowbird Way	0.2	HP chip
Timbers Ct	0.07	HP chip
White Birch Way	0.05	HP chip
Quail Ct	0.05	HP chip
	3.14	263000
Woodfern Rd	1	Reclamation & C
		217000
	miles	total
	4.14	480000
Whiton Rd (South Branch to Tamarack		Reconstruction
Mill asphalt and overlay		Mill & Overlay
Recycle asphalt in place, stabilize and		Reclamation & Overlay
Reconstruction of roadway		Reconstruction
Standard emulsion and aggregate trea		chip
Thin topcoat		Micro pave
Standard chip seal with micro pave top		Cape seal
Rubberized asphalt and aggregate trea		HP chip

2013	**miles**	Treatment
Andover Drive	0.16	Cape seal
Arrowhead Drive	0.71	Cape seal
Bald Eagle Drive	0.6	Cape seal
Blue Jay Court	0.36	Cape seal
Bernard Street	0.84	Cape seal
Country Squire Way	0.5	Cape seal
Howell Drive	0.39	Cape seal
Hummingbird Lane	0.06	Cape seal
Kensington Court	0.05	Cape seal
Kiva Place	0.18	Cape seal
Lexington Ave	0.22	Cape seal
Pine Ridge Drive	0.27	Cape seal
Sharon Ave	0.35	Cape seal
Vail Terrace	0.44	Cape seal
South Horizon Way	0.63	Cape seal
Swan Ct	0.15	Cape seal
Wren Way	0.3	Cape seal
Century Ln	0.24	Cape seal
	6.45	325000
D'Angelo Drive	0.4	HP chip
Narraganset Drive	0.92	HP chip
Old York (Parts)	0.5	HP chip
Centerville Rd	0.11	HP chip
Craig Rd	0.06	HP chip
	1.99	196000
	8.44	
		521000
Shadyside ct	0.16	mill&pave
		28000
Fairview (summer to Cheryl)	0.22	Reclaim and pave
		51000
	miles	total
	8.82	600,000

2012	**miles**	Treatment
Rolland	0.27	Cape seal
Logan	0.19	Cape seal
Summit	0.08	Cape seal
Cedar Grove	1.12	Cape seal
Baird	0.63	Cape seal
Grandview	0.49	Cape seal
Hilltop	0.19	Cape seal
River(ends)	0.89	CAPE
		160000
Horizon	0.94	Micro Pave
Kelly	0.48	Micro Pave
Omni	0.17	Micro Pave
Renya	0.2	Micro Pave
Industrial (county lin	0.72	Micro Pave
Meister (Readingtor	0.49	Micro Pave
	6.86	108000
River (center portio	0.95	HP chip
Otto	0.9	HP chip
Summer	0.46	HP chip
	2.31	176000
	miles	total
	9.17	444000
Engineering		
Old York(by Case)	0.34	Reconstruction
Stony Brook (West	0.52	Reconstruction
Marylynn	0.24	
	1.1	

2011	**miles**	Treatment
Aspen Hill Rd	0.29	Chip
Black Point Rd	0.3	Chip
Branch Drive	0.18	Chip
Chester Ave	0.29	Chip
Clinton St	0.18	Chip
Crestwood Ave	0.2	Chip
Culnen Dr	0.17	Chip
Fremont St	0.22	Chip
Glen Crest Dr	0.32	Chip
Industrial Pkwy(Readington Rd side)	0.48	Chip
Industrial Pkwy(County Line side)	0.72	Chip
Lehman Ln	0.14	Chip
Marshall St	0.28	Chip
Meister Ave(Readington Rd side	0.55	Chip
Rose Way	0.07	Chip
Shaffer St	0.22	Chip
	miles	Total
	4.61	177000
Engineering		
County Line (off Rt 22)	0.7	Reconstruction
Huyler	0.61	Reconstruction
Henry	0.31	Reconstruction
Robbins	0.58	Reconstruction
	2.2	